M.R.O. 1—77,006—8-6-31.

(1) Number of pages

(2) Date of repair

(3) Initials of the Referencer

MADRAS RECORD OFFICE.

Government of Madras.

Public works DEPARTMENT.

G.O. No. 1487 Press/Mis.

254-255

Dated 15-7 182 .

Not to be folded or roughly handled

Proceedings of the Madras Government, Public Works Department,
15th June 1872.

No. 254. Read the following letter from the Superintending Engineer, 8th Division, to the Secretary to Government, Public Works Department, dated Madura, 29th May 1872, No. 902:—

1 Plan.
1 Estimate of Rupees 7,250.
1 Specification Report.

In compliance with the instructions contained in G. O., 18th March 1872, No. 769, and its accompanying Budget, I have the honour to submit herewith, for the sanction of Government, an estimate of Rupees 7,250 for the restoration of a portion of Tiroomala Naick's Palace at Madura.

2. This service is entered in the Provincial and Local Budget of 1872-73 as No. 50, under the heading of "Civil Buildings, Original Works," with an allotment of Rupees 10,000.

3. An estimate of Rupees 10,000 was prepared by the Palace Overseer and was submitted to me through the Range Officer. On referring the matter, however, to the Government Architect, that gentleman informed me that he wished to visit Madura before the estimate was sent in. Mr. Chisholm arrived here yesterday, and he has requested me to submit at once for sanction a portion of the said estimate, namely, that contained in the accompanying estimate, and to state that he will prepare a supplemental estimate for such further work as he proposes to get carried out this year.

4. In order to prevent further delay, I have now authorized the Range Officer to proceed with the work in anticipation of the sanction of Government, and I trust that, under the circumstances, this course will be approved.

No. 255. ORDER THEREON, 15th June 1872, No. 1,487.

CIVIL WORKS, No. 21.

THE Government sanction the estimate of Rupees 7,250 submitted with this letter, and await the further estimate proposed to be furnished for the balance of the grant of Rupees 10,000 included in the current year's Provincial Budget for the restoration of Teroomala Naick's Palace.

(True Extract.)

Captain, R.E.,
Acting Joint Secretary to Government.

To the Superintending Engineer, 8th Division, with Specification.
,, Controller of Public Works Accounts.
,, Consulting Architect.
,, Financial Department.

Exd. S. T. Augustin.

No. 71 of 1872-73

37

Abstract Estimate for the portion to be Restored in Tiroomal Naick's Palace at Madura

Quantity	Particulars of Works	Rate	Amount			Total		
	Waggon Vault							
6406 3/4	Sqre feet of Plaster in Chunam 3 Coats } ℔ Sqre	3-8-"	224	3	9			
1042 1/2	— Do — Cornice work in Chunam ℔ ft	"-2-6	162	14	3			
356 1/4	— Do — Plaster Mouldings do — ℔ ft	"-6-"	133	9	6			
132	Cft granite ashlar Moulded ℔ C-foot	3-"-"	396	"	"			
No 10	Draggons in Chunam Each —	1-8-"	15	"	"			
" 35	Ornamental flowers — " —	2-"-"	70	"	"			
" 2	Volutes in chunam — " —	1-8-"	3	"	"			
" 4	Birds — Do — " —	1-8-"	6	"	"			
" 1	Griffins head in Central Arcades	5-"-"	5	"	"			
" 5	Large Griffins in Chunam Couple	25-"-"	125	"	"			
" 4	— Do — Do — Do —	25-"-"	100	"	"			
" 5	Pillasters in Chunam for Griffins	5-"-"	25	"	"	1,265	11	6
	Octagon Dome							
20256	Sqre feet of plaster in Chunam 3 Coats	3-8-"	708	15	4			
11/9	Cub yds of brick in — Do (above 30 ft)	5-8-"	61	1	9			
2038 1/2	Sqre ft of Cornice Work in Chunam	"-2-6	318	8	3			
1813 1/2	— Do — Pavement concrete & tar — Sqre	8-"-"	145	1	3			
25 5/27	Cub yd of brick in Chunam on edge	4-"-"	100	11	10			
80-9"	Cub feet of teak wrought frames ℔ ft	3-12-"	302	13	"			
848	Sqre feet of Doors & Windows ℔ ft	1-8-"	1272	"	"			
44 3/4	Cyds dismantling Old wall —	"-8-"	22	6	"			
5	Pinacles over Domes —	4-"-"	20	"	"			
6	Irons Ties 1/2" Diameter —	—	100	"	"			
18 1/2	Sqre feet of oil paint 2 Coats for Doors &c	2-"-"	37	"	"			
600	Do of plaster mouldings in Ch:	"-6-"	225	"	"	3313	9	5
						4579	4	11

Quantity	Particulars of Work	Rate	Amount			Total		
	Brought over Rupees					4579	4	11
	The Room on the North side of the Dome.							
49	Sqres of Plaster in Chunam 3 Coats	3-8-"	171	8	"			
145	Cub ft of timber wrough framed Teak	3-12-"	54	1	"			
192	Sqre feet of Door & Windows Teak with fittings	1-8-"	288	"	"			
834¾	Do Pavement 10" bricks	8-"-"	66	12	6			
11 16/27	Cyds of brick on edge in Chunam	4-"-"	46	5	11			
15½	do of walls to be dismantled	"-8-"	7	12	"			
486	Sqre ft Cornice work in Chunam	"-2-6	75	15	"			
100	Do Plaster mouldings	"-6-"	37	8	"			
4/8	Sqres oil Painting for Doors (2 Coats)	2-"-"	8	4	"			
200	lbs of iron bar for Windows ℘ lb	"-2-"	25	"	"	781	2	5
						5360	7	4
	Deduction for work done in last year in the Waggon Vault					122	7	9
						5237	15	7
	Add 5 per Cent for Contingencies					260	"	5
	Salary & allowance for Overseer	"	1380	"	"			
	" Petty Establishment	"	372	"	"	1752	"	"
	Total Estimate Rupees					7,250	"	"

Ricd. Roberts Lieutt Coll R.E.
Superintending Engineer 8th Dn

Supg. Engr's Office 8th Dn
Madura 29th May/72

Compd
 8.R.

5

Pros: 15th June /72 In B No 254.

Enclosure No. 2 in a letter from the Superintending Engineer 8th Division dated 29th May 1872.

No. 903.

To The Offg Secty to Govt D.P.W. Madras.

P.W. 2738/72.

No. 71 of 1872-73

Abstract Estimate for the portion to be Restored in Teroomal Naicks Palace at Madura.

Estimate Rs. 7250 " "

G.O. 15th June /72 No 1587

No 902. Superintg Engineers' Office 8th Dn
Madura 29th May 1872

From
Lieutenant Colonel R. A. Roberts RE
Superintending Engineer
8th Division

To
Colonel C. N. Walker RE
Offg Secretary to Government D.P.W.
Madras.

Enclosures 3
1 Plan
1 Estimate of Rs 7250.
1 Specification
Report

Sir,
In Compliance with the instructions Contained in G.O. 18th March 1872, No 769 and its accompanying Budget, I have the honor to submit herewith for the sanction of Government an Estimate of Rupees 7,250 for the restoration of a portion of Tiroomal Naick's Palace at Madura.

2. This service is entered in the

the Provincial and Local Budget of 1872-73 as No. 50 under the heading of "Civil Buildings Original Works", with an allotment of Rupees 10,000. —

3. An Estimate of Rs 10,000 was prepared by the Palace Overseer and was submitted to me through the Range Officer. On referring the matter however to the Government Architect, that Gentleman informed me that he wished to visit Madura before the Estimate was sent in. Mr. Chisholm arrived here yesterday and he has requested me to submit at once for sanction a portion of the said Estimate viz.t that contained in the accompanying Estimate, and to state that he will prepare a Supplemental Estimate for

Such

such further work as he proposes to get carried out this year. —

4. In order to prevent further delay I have now authorized the Range Officer to proceed with the work in anticipation of the sanction of Government and I trust that under the Circumstances this Course will be approved. —

I have the honor to be
Sir
Your Most Obedient Servant
Richd. H. Roberts Lieut. Col. R.E.
Superintending Engineer 8th C. D.

Compd
882

P. W. ~~Exty~~ 2 Depart.
No 903.

From. (11) No 2738.

The Superintg Engr
8th Division

To. The Offg Secretary to Govt
D.P.W.
Madras.

Dated 29th May 1872
Despatched 30th — do — do
Received 3rd June /72.
Enclosures 3

Submits for the Sanction of Government an Estimate of Rs 7250 for the restoration of a portion of Tirumal Naicke's place at Madura with Certain Explanation.

No 1487 With 4th June /72 an order

Rd 18 March /72 No 423
430

No. 1487

The Government sanction the Estimate of Rs 7250 submitted with this letter, & await the further Estimate prepared to be forwarded for the balance of the grant of Rs 11910 included in the current year's Provincial Budget for the restoration of Tirumala Naick's Palace

Copy to Accountant General, Controller, Consg Architect, Financial Dept

Dated 18/6/72

No. 2738

Govt. of 1872 Madras.

PUBLIC WORKS.

To The Superintending Engr 8th Division

Dated

Recd.

Encl. 2

G. O. 15th June 1872, No. 1487.

Nos. 254 & 255

Tiroomala Naick's Palace at Madura Estd

Rs. 7250 for the restoration of a portion of Tiroomala Naick's palace at Madura, sanctioned with remarks.